

SCOPE OF SERVICES Task 1: Basis of Design Report Task 1.1

Stormwater Model Analysis CMA shall refine the ICPR stormwater model developed during the 2013 Westchester Stormwater Study to allow for a more detailed analysis of the project area. CMA will review and incorporate all of the recent improvements conducted by SWCD since the completion of the previous stormwater study. CMA will subdivide the existing drainage basins further to allow for the more detailed analysis of the project area on a block by block basis. CMA will update the model parameters of the relevant nodes and links within the stormwater model to reflect the revised basin boundaries within the project area. CMA will run the updated stormwater model to obtain peak flood stages, flood durations, and peak discharges for the existing conditions within the project area. CMA will also use the stormwater model to assess the effectiveness of the various potential system improvement alternatives. CMA will run updated stormwater model for various scenarios which will include multiple combinations of the potential system improvement alternatives. CMA will use the stormwater model to compare the effectiveness of each scenario at reducing the peak flood stage and flood duration throughout the project area while also estimating the impact on peak discharge into the Westchester Canal. The model results for the various system improvements scenarios will be included in the Basis of Design Report. CMA shall complete this task within 60 calendar days from the issuance of the Notice to Proceed (NTP) from the City.

Task 1.2 Permit Verification Based on the regulatory requirements, the implementation of the proposed stormwater improvements within the project area will likely be contingent on providing sufficient storage volume for water quality treatment of stormwater runoff prior to discharge into the Westchester Canal and on limiting the peak discharge via the existing stormwater outfalls. CMA shall review, evaluate, and compare the permit restrictions on the various potential system improvement alternatives. CMA will tabulate the maximum water quality volume that could be provided under each potential system improvement alternatives for comparison with the minimum volume per regulatory requirements. CMA will compare the peak discharge under each potential system improvement alternatives with the maximum allowable discharge per regulatory requirements. CMA shall meet with SWCD and with South Florida Water Management District (SFWMD) to present the potential system improvement alternatives for this project and to confirm the permit requirements for each potential system improvement alternatives. The permit requirements for each system improvements scenario will be summarized in the Basis of Design Report for comparison purposes. CMA shall complete this task within 60 calendar days from the issuance of the Notice to Proceed (NTP) from the City.

Task 1.3 Document Research/Review CMA will review all available topographic surveys, atlases, design drawings, and/or record drawings for the existing utilities within the project area to determine the configuration of existing conditions. CMA will also review all plat maps for the project areas to confirm the presence of any utility easements at the locations of the existing stormwater outfalls throughout the neighborhood. If the available plat maps for the neighborhood do not display any utility easement at these outfall locations, additional title searches will be conducted to confirm the presence of existing utility easements at these locations. This scope is limited to title searches for up to 10 parcel locations. CMA will perform necessary site visits to the project area for verification purposes. CMA shall complete this task within 60 calendar days from the Notice to Proceed (NTP) from the City.